

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-11198-00-00
Spot: NWSE Sec/Twnshp/Rge: 31-10S-18W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ANDERSON F Well #: 1
County: ROOKS Total Vertical Depth: 3609 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	133		110 SX
PROD		0		0
PROD	5.5	3609		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/18/2012 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC Phone: (620) 727-3409

Proposed Plugging Method: Ordered 360 sxs 60/40 poz 4% gel:200# hulls
Well was formally known as the # 1 Gasaway 'F'
Operator milled on well for 3 days got to 1404'

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 02/20/2012 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1404' pumped 150 sxs 60/40 poz with 2 hundred # hulls mixed in.
Pulled tubing to 900' pumped 100sxs cement.
Pulled tubing perfed at 700' & 200'.
RIH with tubing to 700' circulated with 50 sxs.
Rigged to 8.625"CSG & pumped 10sxs with 200 # PSI had shut in pressure.
Topped off 5.5" CSG with 10 sxs.
2-20-2012 topped off 5.5"CSG with 40 sxs.

Perfs:


Top	Bot	Thru	Comments
3336	3346		

Remarks: QUALITY WELL SERVICE, INC.

Plugged through: TBG

District: 04

Signed _____



(TECHNICIAN)

CM

FEB 21 2012

RECEIVED
FEB 23 2012
2-23-12
KCC WICHITA
4/28/12

Form CP-2/3