

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-093-00350-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 3-24S-38W  
2859 feet from S Section Line, 2464 feet from E Section Line  
Lease Name: ROHLMAN Well #: 1  
County: KEARNY Total Vertical Depth: 2723 feet

Operator License No.: 5952  
Op Name: BP AMERICA PRODUCTION COMPANY  
Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2587		
SURF	8.625	789		WITH 400 SX CMT
PROD	5.5	2721	0	WITH 1000 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/25/2012 11:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE MARTIN Company: BP AMERICA PRODUCTION Phone: (620) 356-1237

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/25/2012 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING WITH CMT FROM 2576' TO 0' USING 100 SX CLASS C CEMENT W/2% CC AND 250# HULLS FOLLOWED BY 140 SX CLASS C CEMENT & 4% GEL. STAYED FULL. PUMP 5 SX CMT DOWN ANNULUS. BLEW HOLE IN 8 5/8" CASING. ANNULUS FULL.

Perfs:


Top	Bot	Thru	Comments
2654	2672		
2596	2644		
2542	2576		

Remarks: USED CLASS C CEMENT & 4% GEL BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED

FEB 16 2012

KCC DODGE CITY

RECEIVED

FEB 23 2012

KCC WICHITA

Form CP-2/3

✓ 2/28/12

AWD