

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-30295-00-00  
Spot: SESESWNW Sec/Twnshp/Rge: 32-34S-13W  
2823 feet from N Section Line, 1258 feet from W Section Line  
Lease Name: FREI BESSIE ETAL Well #: 1  
County: BARBER Total Vertical Depth: 4930 feet

Operator License No.: 32192  
Op Name: PRIDE ENERGY COMPANY, A GENERA  
Address: P O BOX 701950  
TULSA, OK 74170

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4878		
SURF	8.625	376		WITH 250 SX CMT
PROD	4.5	4930	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/23/2012 8:30 AM  
Plug Co. License No.: 34235 Plug Co. Name: AMIGOS WELL SERVICE INC.  
Proposal Rcvd. from: EDGAR SANCHEZ Company: AMIGOS WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SAND BACK TO 4760' & PUT 4 SX CMT ON TOP OF SANDBRIDGE. CUT OFF & PULL CASING. PLUG AT 660' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2012 1:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1/23/12: NO STRETCH IN CASING. RUN IN HOLE W/CIBP. COULDN'T GET CIBP BELOW 3275'. PULL OUT OF HOLE W/CIBP. BOND LOG 4 1/2" CASING. FOUND CMT FROM 918' UP TO 98' FROM SURFACE. 1/24/12: RUN TBG IN TO 4600'. SPOTTED 50 SX COMMON CEMENT 3% CC & 1/4# FLO SEAL. LET CMT SET. TAG TOP OF CMT AT 3600'. RUN TBG TO 900'. CIRCULATE 4 1/2" CASING TO SURFACE WITH 75 SX CMT. PULLED TBG. TOP OFF 4 1/2" CASING WITH 5 SX CMT. PUMPED DOWN 4 1/2" X 8 5/8" ANNULUS WITH 10 SX CMT. PRESSURED UP TO 600#. HELD.

Perfs:

Top	Bot	Thru	Comments
4814	4842		MISSISSIPPI
4684	4689		KANSAS CITY

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

FEB - 3 2012

KCC DODGE CITY

Signed

Stephen J Pfeifer  
(TECHNICIAN)

RECEIVED

FEB 23 2012

KCC WICHITA

Form CP-12

2/28/12