

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20378-00-00
Spot: S2NW Sec/Twnshp/Rge: 14-30S-42W
3337 feet from S Section Line, 3962 feet from E Section Line
Lease Name: KANSAS UNIVERSITY Well #: 1-14
County: STANTON Total Vertical Depth: 5690 feet

Operator License No.: 32628
Op Name: QUANTUM OPERATING COMPANY
Address: PO BOX 3029
DENVER, CO 80201

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1535		
SURF	8.625	1604		WITH 825 SX CMT
COND	20	50		
PROD	4.5	5683	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/27/2012 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUG AT 1500' WITH 330 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. TAG & CIRCULATE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2012 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 1535'. RUN TBG TO 1500'. PUMP 15 SX GEL, 150# HULLS & 330 SX CMT. GOOD CIRCULATION. TOOH W/TBG. TAG TOC @ 1260'. PULL TO 1000' & SPOT 50 SX CMT. PULL TO 600' & SPOT 50 SX CMT. PULL TO 380' & SPOT 50 SX CMT. PULL TO 30' & SPOT 20 SX CMT. CMT CIRCULATED.

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED COMMON CEMENT & 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
FEB - 7 2012
KCC DODGE CITY

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED
FEB 23 2012
KCC WICHITA

✓ 2/28/12

Form CP-2/3

RAW