

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20419-00-00  
Spot: NWSE Sec/Twnshp/Rge: 24-30S-42W  
2005 feet from S Section Line, 1976 feet from E Section Line  
Lease Name: SULLIVAN Well #: 1-24  
County: STANTON Total Vertical Depth: 5650 feet

Operator License No.: 32628  
Op Name: QUANTUM OPERATING COMPANY  
Address: PO BOX 3029  
DENVER, CO 80201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1516		WITH 675 SX CMT
PKR		5451		
PROD	4.5	5650	0	WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2012 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND PERFS & COVER W/4 SX CMT. RIH W/TBG PUMP 150# HULLS, 15 SX GEL & CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/26/2012 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SAND PERFS TO 5038' & COVER WITH 4 SX CMT. RIH W/TBG TO 1630' & PUMPED 150# HULLS, 15 SX MUD & 130 SX CMT FILLING TO SURFACE. RIH W/1" TBG INSIDE 8 5/8" X 4 1/2" ANNULUS & TAGGED AT 320'. PUMPED 70 SX CMT FILLING TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5524	5532		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
FEB - 2 2012  
KCC DODGE CITY

RECEIVED  
FEB 23 2012  
KCC WICHITA

Form CP-2/3

2/28/12