

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-207-21462-00-00
Spot: SENENESW Sec/Twnshp/Rge: 24-23S-16E
2070 feet from S Section Line, 2952 feet from E Section Line
Lease Name: MAYNARD Well #: 23
County: WOODSON Total Vertical Depth: 990 feet

Operator License No.: 34047

Op Name: RON-BOB OIL LLC

Address: PO BOX 41
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.5	20		20 SX
PROD	2.375	965		20 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2011 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: ROBERT CHRISTENSON Company: _____ Phone: (620) 365-0919

Proposed Plugging Method: RUN 1" INTO 2" TO BOTTOM AND RUN 1" BEHIND 2" TO BOTTOM, THEN CEMENT FROM BOTTOM TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 10/18/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2 3/8" casing to TD. Dug down the backside of the 2 3/8" casing 3' to find cement. Pumped cement through the 1" pipe inside the 2 3/8" casing from TD to surface. Pull 1" up to 500'. Pump cement from 500' to surface. Pull 1" up to 250'. Pump cement from 250' to surface. Pull the rest of the 1" pipe. Top well off with cement. A total of 36 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED
FEB 16 2012 RMD
KCC Chanute Dist. #3

RECEIVED
FEB 23 2012

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed _____

(TECHNICIAN)

✓ 2/28/12