

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-189-22663-00-00
 Spot: N2NW Sec/Twnshp/Rge: 11-35S-35W
 612 feet from N Section Line, 1304 feet from W Section Line
 Lease Name: DON HALL Well #: 1-11
 County: STEVENS Total Vertical Depth: 7001 feet

Operator License No.: 9228
 Op Name: MARLIN OIL CORPORATION
 Address: PO BOX 14630
OKLAHOMA CITY, OK 73113

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4210		WITH 2 SX CMT
CIBP		4410		
CIBP		4495		
CIBP		4585		
SURF	8.625	1664		WITH 575 SX CMT
PROD	4.5	4650	2570	WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/30/2012 10:00 AM
 Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
 Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 4210' WITH 2 SX CMT. CIRCULATE HOLE WITH MUD. SHOOT 4 1/2" CASING. PUMP 50 SX CMT AT 1680', 40 SX CMT AT 580, 10 SX CMT AT 40'.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 01/31/2012 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

SET CIBP @ 4210' WITH 2 SX CMT. CIRCULATED HOLE WITH MUD. SHOT 4 1/2" CASING @ 2570'. 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 580' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4604	4606		
4559	4561		
4550	4552		
4501	4504		
4468	4470		
4452	4454		
4446	4448		
4340	4342		
4252	4342		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
 FEB - 3 2012
 KCC DODGE CITY

Signed Jack MacLaskey
 RECEIVED
 FEB 23 2012
 KCC WICHITA
 (TECHNICIAN)
 2/28/12