

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-10030-00-00  
Spot: NW Sec/Twnshp/Rge: 12-32S-42W  
1320 feet from N Section Line, 3960 feet from E Section Line  
Lease Name: BAILEY Well #: 1-12  
County: MORTON Total Vertical Depth: 3290 feet

Operator License No.: 32638  
Op Name: NADEL AND GUSSMAN LLC  
Address: 15 E 5TH ST STE 3200  
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	699		WITH 400 SX CMT
PROD	5.5	3264	922	WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2012 2:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: TBG STUCK. SHOOT AS LOW AS POSSIBLE & PUMP 25 SX CMT. SHOOT 5 1/2" CASING & PUMP 50 SX CMT AT 720', 50 SX CMT AT 400', & 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/08/2012 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

FREE POINT 2 3/8" TBG AT 2350'. SHOT TBG & PUMPED 25 SX CMT & POH W/TBG, SHOT 5 1/2" CASING AT 922'. PUMPED 50 SX CMT AT 720'. PUMPED 50 SX CMT AT 400'. PUMPED 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
3216	3223		
3176	3181		
3154	3156		
3144	3147		
3114	3130		
3056	3060		
3026	3029		
2996	2998		
2831	2833		
2822	2825		
2816	2818		
2808	2810		GREENWOOD TOP

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED  
FEB 15 2012  
KCC DODGE CITY

RECEIVED  
FEB 23 2012  
KCC WICHITA

Form 2/28/12