

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-00483-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 17-35S-41W
2557 feet from S Section Line, 2415 feet from E Section Line
Lease Name: HAYWARD D Well #: 1
County: MORTON Total Vertical Depth: 2370 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2307		RETAINER
SURF	8.625	360		WITH 200 SX CMT
PROD	5.5	2369		WITH 550 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 01/25/2012 9:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT AT 2260'. 25 SX CMT AT 1500'. 390' TO SURFACE WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2012 2:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 200#HULLS & 25 SX CMT AT 2260'. 1ST PLUG AT 1500' WITH 25 SX CMT.
2ND PLUG WITH 45 SX CMT @ 390' TO SURFACE. PUMP 2 SX CMT DOWN 5 1/2" X 8
5/8" ANNULUAR SPACE.

Perfs:

Top	Bot	Thru	Comments
2340	2346		SQUEEZED
2324	2336		SQUEEZED
2276	2294		CHASE
2260	2270		CHASE

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

FEB - 2 2012

KCC DODGE CITY

RECEIVED

FEB 23 2012

KCC WICHITA

Form CR-20

2/20/12