

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20365-00-00  
Spot: W2 Sec/Twnshp/Rge: 15-34S-40W  
2618 feet from N Section Line, 1347 feet from W Section Line  
Lease Name: LUTHER B Well #: 2  
County: MORTON Total Vertical Depth: 3000 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	531		WITH 350 SX CMT
PROD	4.5	2999	741	WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/30/2012 1:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUG AT 1702' WITH 20 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/30/2012 3:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

WELL HAS JUNK IN HOLE. TAGGED TOP OF FISH @ 1703'. 1ST PLUG CIRCULATED HOLE W/MUD & PUMPED 20 SX CMT AT 1700'. POH W/TBG. SHOT 4 1/2" @ 741'. POH W/CSG. 2ND PLUG RIH W/TBG TO 750' & PUMPED 40 SX CMT. 3RD PLUG AT 560' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2906	2912		COUNCIL GROVE
2884	2894		COUNCIL GROVE
2847	2878		COUNCIL GROVE
2827	2840		COUNCIL GROVE

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

FEB - 2 2012

KCC DODGE CITY

RECEIVED

FEB 23 2012

KCC WICHITA

Form CP-243

✓ 2/28/12