

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20335-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 22-33S-41W
1268 feet from S Section Line, 2571 feet from E Section Line
Lease Name: MOORE Well #: 1
County: MORTON Total Vertical Depth: 2180 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	409		WITH 450 SX CMT
PROD	4.5	2179	994	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/23/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Pumping Method: PUMP 30 SX CMT DOWN 1 1/2" TBG. FREE POINT TBG & CUT. POH W/TBG. SHOOT 4 1/2" CASING & POH. RIH W/TBG TO 1300' & PUMP 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. FILL HOLE WITH CMT FROM 60' TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/25/2012 3:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

****WELL HAS 1 1/2" TBG STUCK**** 1/23/12: PUMPED INTO 1 1/2" TBG AT 800 PSI. NO CIRCULATION OR BLOW ON ANNULUS. SHOT 1 1/2" TBG AT 1740'. UNABLE TO POH. TBG MOVED APPROXIMATELY 20'. UNABLE TO CIRCULATE HOLE OR PULL TBG. SDON 1/24/12: SHOT 1 1/2" TBG AT 1600' & POH W/TBG. RIH W/2 3/8" TBG TO 1600', PUMPED 35 SX CMT. POH W/TBG. LET SET 2 HOURS. TAG TOC @ 1168'. SHOT 4 1/2" CASING AT 994' & POH W/CASING. RIH W/TBG TO 650', PUMPED 135 SX CMT. POH W/TBG. SDON. 1/25/12: TAGGED TOC @ 506'. RIH W/TBG TO 500' & PUMPED 100 SX CMT. POH W/TBG. TAGGED TOC @ 184'. FILLED CASING FROM 60' TO SURFACE WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2082	2148		CHASE

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED

FEB - 2 2012

KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

FEB 23 2012

KCC WICHITA

Form CP-2/3

2/28/12