

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-075-20008-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 4-26S-39W
1324 feet from S Section Line, 1321 feet from E Section Line
Lease Name: O RECTOR Well #: 1
County: HAMILTON Total Vertical Depth: 2740 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA,
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	9.625	725		WITH 350 SX CMT
PROD	7	2740	0	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/26/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RENE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 30 SX CMT AT TOP OF FILL UP. RUN TBG & PACKER TO 1500' & PUMP 50-100 SX CMT IN TO CASING LEAK. PERFORATE AT 750' & CIRCULATE WITH MUD, HULLS & CC. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2012 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAG FILLUP IN 7" CASING AT 2435'. (CASING LEAK APPROX. 1500') PUMP 30 SX CMT AT 2376'. PUMP 100 SX CMT WITH 100# HULLS AT 1520'. NO CIRCULATION. TOO H W/TBG. SDON. 1/27/12: TAG TOC IN 7" CASING AT 1502'. TEST CASING TO 500 PSI. HOLDING. PERFORATE AT 745'. TAKE INJECTION RATE 2 1/2 BPM @ 300# CIRCULATING FLUID TO SURFACE. CIRCULATE 7" & 7" X 9 5/8" ANNULUS FULL OF CMT USING 240 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2672	2690		FT. RILEY
2630	2642		TOWANDA
2587	2590		WINFIELD
2566	2576		WINFIELD
2512	2536		KRIDER

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED CLASS C CMT & 2% GEL BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
FEB -7 2012
KCC DODGE CITY

RECEIVED
FEB 23 2012
KCC WICHITA

Form CP-2/3

✓ 2/28/12
RAWY