

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-207-26753-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 3-24S-17E
1080 feet from S Section Line, 400 feet from W Section Line
Lease Name: SOVOBODA Well #: 13-01
County: WOODSON Total Vertical Depth: 1252 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN RD
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		15 sx
PROD	2.875	1224		185 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/23/2011 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: GREG LAIR Company: _____ Phone: (620) 433-0099

Proposed Plugging Method: Hook on to, squeeze, cement to surface.

Plugging Proposal Received By: _____ WitnessType: PARTIAL
Date/Time Plugging Completed 09/26/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2 7/8" casing to TD. Pumped and circulated cement through the 1" pipe inside the 2 7/8" casing from TD to surface. Pulled the 1" pipe. Topped well off with cement. A total of 71 sacks of portland cement was reported used to plug this well.

RECEIVED
FEB 16 2012 RMD
KCC Chanute Dist. #3

Perfs:

Remarks:

Plugged through: TBG

RECEIVED
FEB 23 2012
KCC WICHITA

District: 03

Signed [Signature]
(TECHNICIAN)

2/28/12