

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-169-20101-00 00

LEASE NAME Johnson #1

WELL NUMBER _____

SPOT LOCATION C NE NW

SEC. 4 TWP. 16 RGE. 3w (E) or (W)

COUNTY Saline

Date Well Completed _____

Plugging Commenced 1/29/86

Plugging Completed 2/12/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Patton Oil Co.

ADDRESS 4th Finan Ctr, Suite 220, Wichita, Ks. 67202

PHONE # (316) 265-0926 OPERATORS LICENSE NO. 5992

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 337' | none |
| | | | | 5 1/2" | 3486' | 2616' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Plugged bottom with sand to 3250' & 5 sacks cement. Shot pipe at 2820', & 2616'

Pulled 67 joints of pipe. Plugged well with 2 hulls, 10 gel, plug, & 125 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chsae, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


Mike Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1986

My Commission expires:



STATE CORPORATION COMMISSION Public

FEB 18 1986

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84



15-169-20101-00-00

GREENWOOD PLAZA NORTH
SUITE 200, 5660 SOUTH SYRACUSE CIRCLE
ENGLEWOOD, COLORADO 80110

PHONE: (303) 773-6016

CRUDE OIL AND
NATURAL GAS PRODUCERS

FOURTH FINANCIAL CENTER
SUITE 220
WICHITA, KANSAS 67202

PHONE: (316) 265-0926

DRILLING REPORT

JOHNSON #1
C NE NW
SECTION 4-T16S-R3W
SALINE COUNTY, KANSAS

ELEVATION: 1305 G.L.

| | |
|-------------|-------------|
| HERRINGTON | 436(+ 874) |
| WINFIELD | 482(+ 828) |
| FT. RILEY | 588(+ 722) |
| COTTONWOOD | 896(+ 414) |
| RED EAGEL | 1011(+ 299) |
| TARKIO | 1403(- 93) |
| HOWARD | 1616(- 306) |
| TOPEKA | 1685(- 375) |
| QUEEN HILL | 1866(- 556) |
| HEEBNER | 1965(- 655) |
| TORONTO | 1988(- 678) |
| DOUGLAS | 2003(- 693) |
| BROWN LIME | 2164(- 854) |
| LANSING | 2174(- 864) |
| MISSISSIPPI | 2818(-1508) |
| OSAGE | 2902(-1592) |
| KINDERHOOK | 3074(-1764) |

2-22-80 Moved in and rigged up.

2-23-80 Set 8 5/8" casing with 225 sxs Common Cement, 3% Calcium Chloride, 2% Gel. Plug Down @ 7:00 P.M. 2/23/80.

2-24-80 DST #1 400' - 500'
Open 30 min., Shut in 30 min.,
Open 30 min., Shut in 30 min.
Recovery: 10' mud with a few specks of oil
IFP 47#-42#, ISIP 59#,
FFP 42#-42#, FSIP 47#
Drilling @ 1025' 2/24/80

2-25-80 Drilling @ 1885'

2-26-80 Drilling @ 2370'

2-27-80 Drilling @ 2765'

2-28-80 Drilling @ 3160'

2-29-80 Drilling @ 3330'
DST #2 3000' - 3330' (MAQUOKETA)
Open 30 min., Shut in 60 min.,
Open 60 min., Shut in 60 min.
Weak Blow
Recovery: 30' Oil Cut Mud
10% Oil some free oil in top

RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1985

CONSERVATION DIVISION
Wichita, Kansas

IFP 35#'23#
ISIP 680#
FFP 42#-23#
5512 207"