


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Saline County. Sec. 4 Twp. 16 Rge. 3 (E) W (W)  
Location as "NE/CNWxSWx" or footage from lines. SE SE NE  
Lease Owner Tom C. Brown  
Lease Name Leander Well No. 1  
Office Address Lindsborg, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 4-16-64 19  
Plugging completed 4-18-64 19  
Reason for abandonment of well or producing formation Depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3375 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	105'	None
				5-1/2"	3340'	2938'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3375', sanded hole to 3330' and dumped 5 sacks of cement @ 3330' with dump bailer. Pulled 5 1/2" casing, checked hole, set rock bridge from 150' to 140' and dumped 25 sacks of cement @ 140'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JUN 8 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 1964

My commission expires May 20, 1964  
Milton J. Volin Notary Public.

15-169-19174-00-01  
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY

Company- DEWESE & SANDERSON  
Farm- Leander No. 1

SEC. 4 T. 16 R. 3W  
SE SE NE

Total Depth. 3375'

Comm. 10-19-54


Comp. 11-1-54

Shot or Treated.

Contractor.

Issued. 12-1-54

County Saline KANSAS



8 5/8"

CASING:

105' com w/100 sx

Elevation. 1293'

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	70-253
lime	283
lime & shale	297
lime	365
shale & shells	465
shale & shells	495
red bed, shale & shells	540
lime & shells	710
lime & shale	880
lime & shale	1000
shale	1040
shale & shells	1390
lime & shale	1420
shale	1545
shale & lime	1675
lime & shale	1825
lime & shale	2075
shale & lime	2230
shale & lime	2435
lime & shale	2600
shale & lime	2825
cherty lime & shale	2845
lime & shale	2910
cherty lime & shale	2975
chert, lime & shale	3003
lime & shale	3070
shale & lime	3135
shale	3213
shale & lime	3338
lime	3370
lime	3375
Total Depth	

Tops: Scout

Mississippi

Maquoketa Dolomite

Viola

2804

3282

3338

3282  
1293  
- 1989 May

Washed Down

3340

Casing

100 Sack Cement

RECEIVED  
STATE CORPORATION COMMISSION

APR 17 1964

CONSERVATION DIVISION  
Wichita, Kansas