

15-169-00559-00-01


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Saline County. Sec. 3 Twp. 16 Rge. 3 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW, SW, SE

Lease Owner Tom Brown Construction, Inc.

Lease Name Martin Well No. 1

Office Address Lindsborg, Kans.

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 12-22-1948

Application for plugging filed July 20 1966

Application for plugging approved August 2 1966

Plugging commenced Aug. 4 1966

Plugging completed Aug. 19 1966

Reason for abandonment of well or producing formation Insufficient production

If a producing well is abandoned, date of last production June 1st 1966

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Maquoketa Dolomite Depth to top 3299 Bottom Unk Total Depth of Well 3302 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Maq Dol	Oil	3297	3302	4 1/2	3302	60'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled back in the pipe with gravel. Dumped 5 sacks of cement. Pulled pipe, and mudded hole to 260'. Set rock bridge; and filled surface with 3 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1966

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self

Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.
Employee (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self

R. R. #4, Hutchinson, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 24th day of Aug., 1966

Notary Public. (Signature) Dorothy Self

My commission expires October 15, 1969



15-169-00559-00-01

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY **H.S. CURRIER**

SEC. **3** T. **16** R. **3W**
LOC. **SW SW SE**

FARM **Martin**

NO. **1**

COUNTY **Saline**
KANSAS

TOTAL DEPTH **3309'**


COMM. **12-12-48**

COMP. **12-22-48**

SHOT OR TREATED

CONTRACTOR **Beardmore Drilg.**

ISSUED **4-23-49**



CASING

20	10	
15	8 5/8	335' w/150 sx cem
12	6	
13	5 1/4	3302' w/55 sx cem.

ELEVATION

PRODUCTION **25 Bbbl.**

FIGURES INDICATE BOTTOM OF FORMATIONS

gravel	69
sand, shale	120
shale, shells	265
sand	275
shale, shells	327
lime, shale	885
shale, shells	1875
shale, lime	2190
shale, lime	2290
lime brkn	2380
lime, shale	2550
lime	2630
lime, shale	2858
chat	2880
chat, chert, lime	3005
cherty lime shale	3035
lime, shale	3160
shale	3195
shale, lime	3270
shale	3300
lime	3309

TOPS: D.F.	
Mississippian	2827
Kinderhook shale	3087
Maquoketa Dolomite	3297

Rotary Total Depth **3299**

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1966
CONSERVATION DIVISION
WICHITA, Kansas

*Sand to 3290' - dump 5 sx
Rock bridge 260' to 250' - 20 ft
Mud to 40' - Rock bridge 40'-30'
Cap with 10 sacks*