

15-169-00020-00-00

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 1 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150 McPherson, Kansas

Lease Name H.T. Johnson Well No. # 1

Location SW SW SW Sec. 5 Twp. 16S Rge. 3 (N) (W)

County Saline Total Depth 3443'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Chase, Kansas License No. # 436

Operation Completed: Hour 4 PM Day 30 Month 8 Year 66

The Above well was plugged as follows:

- 8 5/8"-355'-Circulated w/cement. 4 1/2"-3436 1/2"-Cemented. Sand hole to 3400'.
- 3 Sax.cement 3400' to 3350'. Mud 3350' to 350'. Bridge 350' to 340'.
- 20 Sax.cement 340' to 280'. Mud 280' to 40'. Bridge 40' to 30'.
- 10 Sax.cement 30' to 0. Pulled 3018'-4 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9/1/66
INV. NO. 3848-U