

15-169-00258-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 28 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sterling Drilling Company

Complete Address: Box 129 Sterling, Kansas 67579

Lease Name Anderson "A" Well No. # 2

Location C NW SW Sec. 3 Twp. 16 Rge. 3 (W)

County Saline Total Depth 3505'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Csaing Oulling Co.

Address: Chase, Kansas License No. # 436

Operation Completed: Hour 530 PM Day 25 Month 7 Year 69

The Above well was plugged as follows:

10 3/4"-296'-Circulated w/cement. 5 1/2"-3495'-Cemented. Plug back to 3382'.
Top Perf. 3296'. Sand hole to 3280'. 5 Sax.cement 3280' to 3230'.
Mud 3230' to 295'. Bridge 295' to 285'. 30 Sax.cement 285' to 225'.
Mud 225' to 40'. Bridge 40' to 30'. 15 Sax.cement 30' to 0.
Pulled 2797'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/28/69
INV. NO. 171-W

Signed: [Signature]
Well Plugging Supervisor