


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

_____ Lane _____ County. Sec. 23 Twp. 16S Rge. 27W (H) _____ (W)
Location as "NE/CNW/SW" or footage from lines _____ C SW NE
Lease Owner Cameron Funk
Lease Name Anderson Well No. A-#1
Office Address 702 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-21-64 19_____
Application for plugging filed 12-21-64 19_____
Application for plugging approved 12-21-64 19_____
Plugging commenced 12-21-64 19_____
Plugging completed 12-21-64 19_____
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19_____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols, Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4703 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	139'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 600' 20 sks. cement
Mud to 120' Plug 20 sks. cmnt.
Mud to 40' Plug 1/2 sk. hulls 10 sks. cmnt.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1964

12-28-1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 64

Wanda Dinkels
Notary Public.

My commission expires April 1, 1967

15-101-00069-00-00

DRILLER'S LOG

COMPANY: Cameron Funk
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: ANDERSON A-#1
 LOCATION: C SW NE Sec. 23-16S-27W
 LANE COUNTY, KANSAS
 COMMENCED: 12-9-64
 COMPLETED: 12-21-64

0	40	Surface Soil, Sand & Clay
40	57	Clay
57	105	Sand
105	1270	Shale
1270	1500	Shale & Redbed
1500	1540	Anhydrite
1540	2100	Shale & Shells
2100	2130	Anhydrite
2130	2600	Shale
2600	3150	Lime & Shale
3150	3360	Lime
3360	3820	Lime & Shale
3820	4703	Lime
	<u>4703</u>	<u>Rotary Total Depth - D. & A.</u>

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1964
12-28-1964
CONSERVATION DIVISION
Wichita, Kansas

Set 8 5/8" used surface casing @ 139' with 110 sacks 60-40 Posmix


I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Anderson A-#1 well, located C SW NE of Section 23, Township 16 South, Range 27 West, Lane County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 23rd day of December, 1964.



Ulanda Nichols

Ulanda Nichols

My Commission Expires
April 1, 1967