

15-101-20724-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY _____ LANE _____ SEC. 20 TWP. 16S RGE. 27W E/W
Location as in quarters or footage from lines:
SW NE

Lease Owner KRM PETROLEUM CORPORATION
Lease Name CAUGHRON Well No. 1-20
Office Address 1900 Grant, Suite 300, Denver, CO 80203
Character of Well (Completed as Oil, Gas or Dry Hole): DRY HOLE
Date Well Completed 11-27-82
Application for plugging filed 12-6-82
Plugging commenced 11-27-82
Plugging completed 11-27-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? PERMISSION WAS OBTAINED

Name of Conservation Agent who supervised plugging of this well STEVE DURANT
Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
SURFACE CASING	6 Jnts.	0	278	8 5/8"	J-55	


Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

The Caughron #1-20 was plugged with 140 sacks, 50/50 Poz. Mix, 4% Gel, 3% CC. First
plug was staged at 1500' with 70 sacks cement. Second plug at 270' with 40 sacks
cement, Third plug at 40' with 10 sacks of cement. Ten sacks in the Rat Hole, and
ten sacks in the Mouse Hole. Final plug was down at 8:30 PM on November 27, 1982.
Plugging order were given by the KCC of Dodge City, Halliburton was in charge of
cementing.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HALLIBURTON

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Arnie Little, Vice President (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Arnie Little
P. O. Box 18611, Wichita, KS 67207
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 19 82

MY APPOINTMENT EXPIRES NOV. 28, 1984
My Commission expires: _____

Mary Kay Oeding
MARY KAY OEDING Notary Public
RECEIVED
STATE CORPORATION COMMISSION
12-07-1982
DEC 7 1982
CONSERVATION DIVISION
Wichita, Kansas

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

WAYNE L. KIRKMAN
PRESIDENT
KIRBY C. EVERS
VICE-PRESIDENT

WELL LOG

15-101-20724-00-00



WELL NAME: CAUGHRON #1-20

WELL LOCATION: SW SE, SEC 20-16S-27W

LANE COUNTY KANSAS

OPERATOR: KRM PETROLEUM CORPORATION

COMMENCED: 11-21-82

CONTRACTOR: ALDEBARAN DRILLING CO., INC.

COMPLETED: 11-28-82

CASING RECORD: 8 5/8" set at 278'

FORMATION:

FROM:

TO:

DIRT	0	41
RED BED	41	288
SAND & SHALE	288	800
SAND, SHALES, REC ROCK	800	2100
RED BED	2100	2124
LIME AND SHALE	2124	4565
LIME & SHALE, MISSISSIPPI	4565	4640


RECEIVED
STATE CORPORATION COMMISSION
12-07-1982
DEC 7 1982

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
SW NE, SECTION 20-16S-27W, LANE COUNTY KANSAS TO THE BEST OF MY

KNOWLEDGE AND BELIEF



ALDEBARAN DRILLING CO., INC.

[Signature]

SUBSCRIBED AND SWORN TO BEFORE ME THIS 6th DAY OF December 1982.

MY APPOINTMENT EXPIRES NOV. 28, 1984

MY APPOINTMENT EXPIRES: _____

Mary Kay Oeding
MARY KAY OEDING NOTARY PUBLIC