

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-101-217560000

LEASE NAME Gates "B"

WELL NUMBER 1

1,650 Ft. from <sup>N</sup> Section Line

990 Ft. from E Section Line

SEC. 19 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 3-23-98

Plugging Commenced 3-23-98

Plugging Completed 3-24-98

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

RECEIVED  
KANSAS CORP.  
04-02-1998  
1998 APR -2 P 1:00  
Resources, Inc.

LEASE OPERATOR Rheem Resources, Inc.

ADDRESS 101 S. Main, Suite 505, Wichita, KS. 67202-3738

PHONE/(316) 262-5099 OPERATORS LICENSE NO. 5184

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-9-98 (date)  
by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,640'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	210'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid w placed and the method or methods used in introducing it into the hole. If cement or other plu were used, state the character of same and depth placed, from feet to feet each se  
Push plug to 2,190', spot 50 sax cement thru drill pipe. Push plug to 1,360', spot 80 sax cement thru drill pipe. Push plug to 650', spot 40 sax cement thru drill pipe. Push plug to 240', spot 40 sax cement thru drill pipe. Push wiper plug to 40', dump 10' sax cement to collar. Dump 15 sax ement down rat hole and 10 sax cement-down mouse-hole. Plug down @1:00AM  
245 sax 60-40 poz., 6% Gel, # Floseal/sax.

Name of Plugging Contractor Shields Drilling Co., division License No. 5184  
of Shields Oil Producers, Inc.  
Address 326 Main, Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rheem Resources, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. Contractor  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Jack P. Beeman  
326 Main  
(Address) Russell, KS., 67665

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 98

Ruth Phillips  
Notary Public

My Commission Expires: \_\_\_\_\_

