

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,658-0000

LEASE NAME Ewing

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1,650 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 18 TWP. 16 RGE. 27 (X) or (W)

COUNTY Lane

Date Well Completed 8-5-93

Plugging Commenced 8-5-93

Plugging Completed 8-5-93

LEASE OPERATOR Staab Oil Co.

ADDRESS 1960 280th Avenue, Hays, KS. 67601

PHONE#(913) 625-3013 OPERATORS LICENSE NO. 6037

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-5-93 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4,582'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	225'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spot:50 sax cement @2,130' thru drill pipe. Push bridge plug to 1,300', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 740', spot 30 sax cement on plug thru drill pipe. Push plug to 240', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Contractor or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 17th day of August **RECEIVED** 93

STATE CORPORATION COMMISSION

My Commission Expires:



Notary Public

AUG 18 1993
08-18-1993
CONSERVATION DIVISION
Wichita, Kansas 67202
EP-4
05-88



Shields


WELL LOG

15-101-21658-00-00

Russell, Kansas

Operator: Staab Oil Co.
Well: Ewing #1
Commenced: July 26, 1993
Completed: August 5, 1993
Contractor: Shields Drilling Co.

Well Description: SW NE SE
Sec. 18-16S-27W
Lane Co., Kansas



CASING RECORD
Size Run Pulled
8 5/8" 225' Cmt'd. w/160 sax

Elevation: 2,721' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand	168'
Shale	251'
Shale & sand	1,972'
Shale	2,133'
Anhydrite	2,168'
Shale	2,474'
Shale & lime	3,980'
Lime	4,582' RTD

Notes

RECEIVED
STATE COOPERATION COMMISSION
AUG 18 1993
08-18-1993
CONSERVATION DIVISION
Wichita, Kansas