

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-101-21,685-00-00

LEASE NAME Gates "A"

WELL NUMBER 8-18

330 Ft. from ^N Section Line

990 Ft. from E Section Line

SEC. 18 TWP. 16 RGE. 27 (E) or (W)

COUNTY Lane

Date Well Completed 9-15-94

Plugging Commenced 9-15-94

Plugging Completed 9-15-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Staab Oil Co.

ADDRESS 1960 280th Avenue, Hays, KS. 67601

PHONE#(913) 625-3013 OPERATORS LICENSE NO. 6037

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-15-94 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,463'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	238'	Cmtd. w/200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Spot 50 sax cement @2,060' thru drill pipe. Push bridge plug to 1,350', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 600', spot 40 sax cement on plug thru drill pipe. Push plug to 260', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 160

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman

(Employee of ~~Operator~~ or ~~Operator~~) c

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 21st day of September, 19 94

My Commission Expires:



Notary Public



Shields


15-101-21685-00-00

Russell, Kansas

WELL LOG

Operator: Staab Oil Co.
 Well: Gates "A" #8-18
 Commenced: September 6, 1994
 Completed: September 15, 1994
 Contractor: Shields Drilling Co.

Well Description: NW NE NE
 Sec. 18-16S-27W
 Lane Co., KS.



CASING RECORD

Size	Run	Pulled
8 5/8"	238'	Cmtd. w/200 sax

Elevation: 2,603' KB

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	2,027'
Anhydrite	2,062'
Shale	2,295'
Shale & lime	3,737'
Lime	4,463' RTD

Notes

N
 RECEIVED
 PERMISSION
 9. 1994
 S I S I O N