

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-101-21,701-00-00

LEASE NAME Ewing

WELL NUMBER 2

2,310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 18 TWP. 16 RGE. 27 (X) or (W)

COUNTY Lane

Date Well Completed 4-25-95

Plugging Commenced 4-25-95

Plugging Completed 4-25-95

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Staab Oil Co.

ADDRESS 1607 Hopewall Road, Hays, KS. 67601

PHONE#(913) 625-5013 OPERATORS LICENSE NO. 6037

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-25-95 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4,570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	233'	Cmtd. w/200 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Spot 50 sax cement @2,130' thru drill pipe. Push bridge plug to 1,290', spot 80 sax cement on plug thru drill pipe. Push bridge plug to 690', spot 40 sax cement on plug thru drill pipe. Push plug to 270', spot 40 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax on plug. Dump 15 sax cement down rathole and 10 sax cement down mouse hole.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Staab Oil Co.

STATE OF KANSAS COUNTY OF RUSSELL

Jack P. Beeman

(Employee of Operator) or Operator of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack P. Beeman, Sr. - Trust

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1995

Ruth Phillips
 Notary Public

My Commission Expires:





Shields


15-101-21701-00-00

Russell, Kansas

WELL LOG

Operator: Staab Oil Company
 Well: Ewing #2
 Commenced: March 14, 1995
 Completed: March 25, 1995
 Contractor: Shields Drilling Co.

Well Description: NE NE SE
 Sec. 18-16S-27W
 Lane County, Kansas



Elevation: 2,681' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	233'	Cmtd. w/200 sax

..... Figures Indicate Bottom of Formations

Sand & shale	236'
Shale	415'
Shale & sand	2,050'
Shale	2,096'
Anhydrite	2,130'
Shale	3,365'
Lime & shale	3,910'
Lime	4,570' RTD

RECEIVED
 KANSAS CORPORATION COMMISSION
 MAY 09 1995
 CONSERVATION DIVISION
 WICHITA, KS