


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Lane \_\_\_\_\_ County. Sec. 14 Twp. 16S Rge. 27W (A) \_\_\_\_\_ (W) \_\_\_\_\_  
Location as "NE/CNW/SW" or footage from lines C NE SW  
Lease Owner Pet-Ex Company  
Lease Name Anderson Well No. 1  
Office Address 300 Insurance Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed January 7, 1961  
Application for plugging filed January 7, 1961  
Application for plugging approved January 7, 1961  
Plugging commenced January 7, 1961  
Plugging completed January 7, 1961  
Reason for abandonment of well or producing formation D & A



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	308'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
Set bottom plug at 300' with  
20 sx cement and 1/2 sx hulls.  
Set top plug at 35' with 1/2  
sx hulls and 10 sx cement.  
Cemented in rat hole with  
2 sx.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 20 1961  
CONSERVATION DIVISION  
Wichita, Kansas  
06-20-1961

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173 - Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
George A. Angle (employer or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George A. Angle  
580 Fourth Nat'l Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of January, 19 61



Mafine Head  
Notary Public.

My commission expires 11-17-62

15-101-00009-00-00

DRILLERS LOG

No. 1 Anderson

JUN 20 1961  
06-20-1961  
CONSERVATION DIVISION  
Wichita, Kansas

CASING RECORD: COMPANY: Met-Ex Company DESCRIPTION: C ND GW  
 8 5/8" @ 308' CONTRACTOR: Red Tiger Drilling Co. 14-168-277  
 w/200 sx cement Lane County  
 Kansas  
 COMMENCED: December 21, 1960 ELEVATION:  
 COMPLETED: January 7, 1961  
 TOTAL DEPTH: 4718'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	45	
Shale Shells	45	295	
Blue Shale	295	308	
Chalky	308	360	
Blue Shale Shells	360	355	
Shale Red Bed	355	975	
Sand	975	1080	
Shale Shells	1080	1505	
Shale & Shells	1505	1845	
Shale & Lime	1845	2090	
Anhydrite	2090	2150	
Shale Shells	2150	2595	
Lime & Shale	2595	2730	
Shale Shells	2730	2890	
Lime Shale	2890	2965	
Lime & Shale	2965	3050	
Shale Shells	3050	3140	
Lime Shale	3140	3412	
Shale Lime	3412	3660	
Shale Shells	3660	3790	
Shale Lime	3790	3865	
Shale & Lime	3865	3985	
Lime	3985	4285	
Lime Shale	4285	4360	
Lime & Shale	4360	4445	
Lime	4445	4565	
Lime Chert	4565	4585	
Chert & Shale	4585	4620	
Lime	4620	4705	
Lime & Chert	4705	4718	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

George A. Angle  
George A. Angle

Subscribed and sworn to before me this 10th day of January, 1961.

Maryne Head  
Notary Public



My Commission Expires:

11-17-62