

ORIGINAL

STATE CORPORATION COMMISSION OF KANSAS
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
ACO-1 WELL HISTORY
DESCRIPTION OF WELL AND LEASE

API NO. 15- 101-21,714 -00-00

County Lane

NE NW SW _____ Sec 8 Twp 16 Rge 27 X W

2310 Feet from S /N (circle one) Line of Section

4290 Feet from E /W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
NE SE NW or NE (circle one)

Lease Name J R Ewing Well # #6

Field Name unnamed

Producing Formation None

Elevation: Ground 2665 KB 2670

Total Depth 4580 PBDT _____

Amount of Surface Pipe Set and Cemented at 212.27 Feet

Multiple Stage Cementing Collar Used? _____ Yes X No

If yes, show depth set _____ Feet

If Alternate II completion, cement circulated from _____

feet depth to _____ w/ _____ sx cmt

Operator: License # 5011

Name: Viking Resources, Inc.

Address: 105 S. Broadway, Ste 1040

City/State/Zip: Wichita, KS 67202-4224

Purchaser: N/A

Operator Contact Person: Shawn Devlin

Phone: (316) 262-2502

Contractor: Name: Abercrombie RTD, Inc.

License: 30684

Wellsite Geologist: Scott Oatsdean

Designate Type of Completion

X New Well _____ Re-Entry _____ Workover _____

_____ Oil _____ SWD _____ SLOW _____ Temp. Abd.

_____ Gas _____ ENHR _____ SIGW

X Dry _____ Other (Core, WSW, Expl., Cathodic, etc.)

If Workover/Re-Entry: old well info as follows:

Operator: _____

Well Name: _____

Comp. Date _____ Old Total Depth _____

_____ Deepening _____ Re-perf. _____ Conv. to Inj/SWD

_____ Plug Back _____ PBDT

_____ Commingled _____ Docket No. _____

_____ Dual Completion _____ Docket No. _____

_____ Other (SWD or Inj?) _____ Docket No. _____

10/11/95 10/17/95 10/18/95
Spud Date Date reached TD Completion Date

Drilling Fluid Management Plan D&A 11-27-96
(Data must be collected from the Reserve Pit)

Chloride Content 6500 ppm Fluid volume 1000 bbls

Dewatering method used Evaporate

Location of fluid disposal if hauled offsite: _____

RECEIVED
KANSAS CORPORATION COMMISSION
Operator Name _____

RELEASED

Lease Name 10-18-1995
OCT 18 1995 DEC 18 1996
License No. _____

CONSERVATION DIVISION FROM CONFIDENTIAL
Quarter Sec DIVISION Twp. S Rng. E/W
WICHITA, KS

County _____ Docket No. _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover, or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature Shawn P. DeL...

Title Vice President Date 10/18/95


Subscribed and sworn to before me this 18 day of October

19 95

Notary Public Paula R. Dunagan

Date Commission Expires March 2, 1997

K.C.C. OFFICE USE ONLY
F Letter of Confidentiality Attached
C Wireline Log Received
C Geologist Report Received
Distribution
 KCC SWD/Rep NGPA
 KGS Plug Other
(Specify)



DRILL STEM TEST RESULTS J R Ewing ##6 NE NW SW Sec 8 T 16 R 27 W, Lane County, Kansas

DST #1 Interval 4120-4150
Times 30-30-30-30

API#15-101-21714

ORIGINAL

IFP 55-55 FFP 68-68 ISIP 970 FSIP 932 IHP 1978 FHP 1940 BHT 117 Degrees
Recovery: 1st open weak blow died in 12 min
Recovery: Rec 15' VSOCM

CONFIDENTIAL

DST #2 Interval 4150-4180
Times 30-30-30-30

IFP 55-55 FFP 68-68 ISIP 203 FSIP 217 IHP 2029 FHP 1991 BHT 115 Degrees
Recovery: 1st open weak blow died in 18 min
Recovery: Rec 15' VSOCM

DST #3 Interval 4430-4470
Times 30-45-45-60

IFP 26-36 FFP 31-42 ISIP 433 FSIP 852 IHP 2209 FHP 2200 BHT 123 Degrees
Recovery: 1st open BTS throughout, 2nd open Blow to 4"
Recovery: Rec 180' GIP, 30' OCM (30%)

RECEIVED
KANSAS CORPORATION COMMISSION

RELEASED

OCT 18 1995

DEC 18 1996

CONSERVATION DIVISION
WICHITA, KS

FROM CONFIDENTIAL

ALLIED CEMENTING CO., INC.

CONFIDENTIAL

2911

O P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Ness City

ORIGINAL

DATE <u>10-11-95</u>	SEC <u>8</u>	TWP <u>16</u>	RANGE <u>27</u>	CALLED OUT <u>2:00 PM</u>	ON LOCATION <u>6:00 P.M.</u>	JOB START <u>7:00 P.M.</u>	JOB FINISH <u>7:15 P.M.</u>
LEASE <u>J.R. Ewing</u>	WELL # <u>6</u>		LOCATION <u>Pandennis 20-wents</u>			COUNTY <u>Lane</u>	STATE <u>KS</u>

OLD OR NEW (Circle one)

CONTRACTOR Allegrombie

TYPE OF JOB Surface

HOLE SIZE 12 1/2" T.D. 213

CASING SIZE 8 3/4" (25*) DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 15

PERFS.

OWNER Same

CEMENT

AMOUNT ORDERED 18560/40243

COMMON	<u>111</u>	@	<u>6.10</u>	<u>677.10</u>
POZMIX	<u>74</u>	@	<u>3.15</u>	<u>233.10</u>
GEL	<u>3</u>	@	<u>9.50</u>	<u>28.50</u>
CHLORIDE	<u>6</u>	@	<u>28.00</u>	<u>168.00</u>

EQUIPMENT

PUMP TRUCK CEMENTER Mike

224 HELPER Bob

BULK TRUCK DRIVER Bill

116

BULK TRUCK DRIVER

#

HANDLING	<u>185</u>	REL	<u>AS/185</u>	<u>194.25</u>
MILEAGE	<u>40</u>			<u>296.00</u>

RECEIVED
KANSAS CORPORATION COMMISSION DEC 1 8 1996

TOTAL \$1596.95

OCT 18 1995 FROM CONFIDENTIAL

REMARKS:

Run 547s 8 3/4" 25* casing - broke circulation with rig - cemented with 18560/40222
Run 547s with 12 1/2" BBI fresh H₂O cement and circulate.

Thank you
Allied Cementing
Mike, Bob, Bill

SERVICE

DEPTH OF JOB	<u>212</u>			
PUMP TRUCK CHARGE				<u>445.00</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>40</u>	@	<u>2.35</u>	<u>94.00</u>
PLUG	<u>TWP</u>	@	<u>45.00</u>	<u>45.00</u>

TOTAL \$584.00

FLOAT EQUIPMENT

CHARGE TO: Uiking Resources Inc.

STREET 105 S. Broadway #1040

CITY Wichita STATE Ks. ZIP 67202

	@		
	@		
	@		
	@		

ALLIED CEMENTING CO., INC. 2915

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

CONFIDENTIAL

SERVICE POINT: Ness City

ORIGINAL

DATE <u>10-17-95</u>	SEC <u>8</u>	TWP. <u>16</u>	RANGE <u>27</u>	CALLED OUT <u>6:15 PM</u>	ON LOCATION <u>8:00 PM</u>	JOB START <u>10:45 PM</u>	JOB FINISH <u>12:45 AM</u>
LEASE <u>J.R. Ewing</u>	WELL# <u>6</u>	LOCATION <u>Pendennis 20-1/2 W 16 N</u>			COUNTY <u>Case</u>	STATE <u>KS.</u>	

OLD OR (NEW) (Circle one)

CONTRACTOR Chercomline

TYPE OF JOB R. Plug

HOLE SIZE 7 7/8" TD. 4580'

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2" DEPTH 2130

TOOL _____ DEPTH _____

PRESS. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

OWNER Same

CEMENT

AMOUNT ORDERED 235 60/40 6798 4 7 10

COMMON _____ @ _____

POZMIX _____ @ _____

GEL _____ @ _____

CHLORIDE _____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

HANDLING _____ @ _____

MILEAGE _____

TOTAL _____

EQUIPMENT

PUMP TRUCK CEMENTER Mike

224 HELPER Mike

BULK TRUCK

199 DRIVER Bill

BULK TRUCK

_____ DRIVER _____

REMARKS:

1st Plug at 2130 w/ 50SKs

2nd Plug at 1075 w/ 30SKs

3rd Plug at 550 w/ 40SKs

4th Plug at 230 w/ 40SKs

5th Plug at 40 w/ 10SKs

Ret. Hole at 155K0

Thank you

Mike & Bill

SERVICE

DEPTH OF JOB 2130'

PUMP TRUCK CHARGE _____

EXTRA FOOTAGE _____ @ _____

MILEAGE _____ @ _____

PLUG Old Hole Plug _____ @ _____

_____ @ _____

_____ @ _____

TOTAL RELEASED

CHARGE TO: Viking

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

DEC 1 8 1996

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 18 1995

CONSERVATION DIVISION
WICHITA, KS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Les Roberts

_____ @ _____

_____ @ _____ FROM CONFIDENTIAL

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS