

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 87-24

LOCATION 5 1/2 - 3 1/2 - 3 E

SEC. 8 TWP. 16 RGE. 1 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Swisher

Operator F.S. Williams Address M^cPherson Kans

Field ✓ County Saline

Total Depth 2687 Feet.

(Describe briefly the manner in which the well was plugged)

Sand to 2665
6 sack cement at 2665
Mud to 120
Bridge 120 to 110
15 sack cement at 110
Mud to 10'
5 sack cement at top of surface
pipe.

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1951
CONSERVATION DIVISION
Wichita, Kansas

Paul Swisher
District Conservation Agent

Date 7-11-51

PLUGGING
FILE SEC. 8 T. 16 R. 1W
BOOK PAGE 87 LINE 29

BERT SELF

Operator of Hydraulic Casing Pulling Units

15-169-00709-0000

419 EAST SIXTH STREET

Hutchinson, Kansas

July 6, 1951

Mr. F. S. Williams
McPherson, Ks.

Plugging report for the Gypson Well: -

*Swisher #3
S 1/2 N 1/2 NE - 8-16-1W
Saline Co. Ks.*

Started: June 26, 1951

Completed: July 3, 1951

Supervised: - Mr. Ruel Durkee

Filled hole back to bottom of the 5 $\frac{1}{2}$. Dumped 6 sacks of cement. Shot pipe off at 2464'. Pulled pipe and mudded hole to 150'. Set rock bridge and 150' and dumped 15 sacks of cement. Finished mudding hole and put 5 sacks of cement at top of surface.

Yours truly,

Bert Self

Bert Self

BS:ds

RECORDED
STATE CORP. COMMISSION

AUG 8 X 1951
CONSE

PLUGGING		
FILE	SEC	T-R
BOOK	PAGE	LINE