

15-101-20073-0000

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1973
10-26-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Patrick Petroleum Corporation,

Complete Address Suite 300, 220 W. Douglas, Wichita, Kansas.

Lease Name Speck Well No. 1

Location NE-SE-NW Sec. 1 Twp. 17 Rge. (E) (W) 28

County Lane Total Depth 4367'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Bldg., Wichita, Ks License No.

Operation Completed: Hour 11:00 AM Day 23 Month 10 Year 1973

The above well was plugged as follows:

333'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 110 Cu. Ft. cement
thru DP from 950' to 625'. Pulled DP to 340' and displaced 30 Cu. Ft. cement thru DP.
from 340' to 265'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 10/30/73

Signed: H. G. Nichols
Well Plugging Supervisor

INV. NO. 8076-W

INVOICED