

15-101-20050-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1973  
2-27-73  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company,

Complete Address 415 Page Court, 200 West Douglas, Wichita, Kansas.

Lease Name Stover Well No. 1

Location NE-SW Sec. 8 Twp. 17 Rge. (E) (W) 28

County Lane Total Depth 4640'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 475 Page Ct., 200 W. Douglas, Wichita, Kansas. License No.       

Operation Completed: Hour 3:15 AM Day 26 Month 2 Year 1973

The above well was plugged as follows:

244'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dechale  
Well Plugging Supervisor

INVOICED

DATE 2/28/73  
INV. NO. 7065-4