

15-101-00041-0600

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasRECEIVED
STATE CORPORATION COMMISSION
NOV 12 1962
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Helmerich & Payne

Complete Address: Box 255 Garden City, Kansas

Lease Name Grusing Well No. 1

Location NE SW NE Sec. 9 Twp. 17 Rge. (E) (W) 28

County Lane Total Depth 4663

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Same & Halliburton

Address: same License No.

Operation Completed: Hour 5AM Day 8 Month 11 Year 62

The Above well was plugged as follows:

8 5/8" 318' circulated with cement.

Circulated hole with heavy mud, set plug at 660', displaced 20 sax

cement through drill pipe, heavy mud to 240', set plug and 20 sax

cement through drill pipe, heavy mud to 35', set plug, hulls and filled

to bottom cellar with cement.

Cementing by Halliburton Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging SupervisorDATE 11/12/62INV. NO. 5996-W