

~~KANSAS~~

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1974  
6-17-74  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil Co., Inc.

Complete Address Rt. #2 Victoria, Kansas

Lease Name Schneider Well No. 1

Location C. W/2 E/2 NW/4 Sec. 12 Twp. 17 Rge. (E) (W) 28

County Lane Total Depth 4650'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 12 N Day 13 Month 6 Year 1974

The above well was plugged as follows:

RTD 4650' 8 5/8 csg set at 201' cwc 150 sk. Cmt. Mat. 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 1200' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 6/18/74

INV. NO. 9316-W