

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
DEC 12 1973
12-12-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.
Complete Address Box 18407 Wichita, Kansas
Lease Name Davis "B" Well No. 3
Location A/C of SW SE Sec. 13 Twp. 17 Rge. (E) (W) 28
County Lane Total Depth 4640'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling
Address Wichita, Kansas License No.
Operation Completed: Hour 11:45 A Day 10 Month 12 Year 1973

The above well was plugged as follows:

RTD 4640' 8 5/8 csg set at 334' cwc 225 sk. Cem. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1000' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 12/12/73
INV. NO. 8292-U