

15 101 20084 0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 6 1974
3-6-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name O. A. Sutton,
Complete Address 800 Sutton Place, Wichita, Kansas.
Lease Name Waterson Well No. 1
Location CSE-NE Sec. 13 Twp. 17 Rge. (E) (W) 28
County Lane Total Depth 4640'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated Lost Hole
Plugging Contractor Gabbert-Jones, Incorporated,
Address 830 Sutton Place, Wichita, Kansas License No.
Operation Completed: Hour 9:15 AM Day 1 Month 3 Year 1974

The above well was plugged as follows:

393'--8 5/8" Surface casing, cement circulated with 250 Sx.
4619'--5 1/2" casing cemented on bottom with top of cement @ 3800'. 5 1/2" casing collapsed
@ 180', broke circulation around but was unable to pull. 5 1/2" casing shot off @ 1350'.
Pulled 5 1/2" casing to 975' and displaced 110 Cu. Ft. cement thru 5 1/2". Pulled 5 1/2" to
400' and displaced 30 Cu. Ft. cement thru 5 1/2". Pulled 5 1/2" casing, set bridge @ 40'
with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. [Signature]
Well Plugging Supervisor

DATE 3/6/74
INV. NO. 8707-W