

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00820-00-00
Spot: CE2E2NW Sec/Twnshp/Rge: 30-15S-3W
1320 feet from N Section Line, 4950 feet from E Section Line
Lease/Unit Name: LARSON Well Number: 5
County: SALINE Total Vertical Depth: 3440 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN
GENESEO, KS 67444

Conductor Pipe: Size _____ feet: 8 1/2
Surface Casing: Size 8.625 feet: 315
Production: Size 5.5 feet: 3440
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2002 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,340' and top with 5 sxs. cement. Shoot pipe off and pull same. Build bridge at 365' and fill casing with slurry mix to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/27/2002 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Hit solid bridge at 165'. Rigged up and drilled on bridge to 175'. Drilling cuttings were cement. Shot casing off and pulled same. Filled casing with 5 yards slurry mix from 175' to the surface.

RECEIVED
KCC DISTRICT #2
OCT 29 2002
WICHITA, KS

Remarks: USED SLURRY MIX BY SMOKEY VALLEY CONCRETE INC. INVIOCE #728.

Plugged through: CSG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 10-31-02

INV. NO. 2003060721