

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-169-00822-00-01
Spot: CS2SWNW Sec/Twnshp/Rge: 30-15S-3W
2970 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: LARSON Well Number: 7
County: SALINE Total Vertical Depth: 3450 feet

Operator License No.: 4560
Op Name: PLACE OIL CO.
Address: 505 STEWART PLACE
LAMAR, CO 81052

Conductor Pipe: Size feet: \$112.13
Surface Casing: Size 10 feet: 361
Production: Size 6 feet: 3450
Liner: Size feet:

Well Type: EOR UIC Docket No: E14385.2 Date/Time to Plug: 08/27/2002 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,350' and top with 7 sxs. cement. Shoot pipe off and pull same. Build bridge at 410' and fill with cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/30/2002 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,335' and topped with 7 sxs. cement. Shot pipe off at 1,925' and pulled same. Built bridge at 415', bailed casing dry, and filled with 8 yards slurry mix to the surface.

RECEIVED
KCC DISTRICT #2

OCT 29 2002

WICHITA, KS

Remarks: USED SLURRY MIX BY SMOKEY VALLEY CONCRETE INC. INVIOCE #755.

Plugged through: CSG

District: 02

Signed Michael R Wilson
(TECHNICIAN)

INVOICED

DATE 10-31-02

WEL. NO. 2003060724