

7-3

160
R

5-060206

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-169-00484-00-00

API NUMBER: drlid 4/17/53

NW SW SE, SECTION 32 TOWNSHIP 15 RANGE 3W

OPERATOR LICENSE # 5563 990 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR D & R Oil Properties
NAME & 100 Laurel Court
ADDRESS McPherson, KS 67460

LEASE NAME: Martinson #1
COUNTY: Saline
WELL TOTAL DEPTH: 3377' -109.75
PIPE: 5-1/2" @ 3374'
SURFACE CASING: 8-5/8" @ 319'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Sunflower Well Service
ADDRESS: 408 N. 4th, Canton, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: am DAY: 3 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Dennis Perera
COMPANY NAME: D & R Oil Properties PHONE: _____

WERE: Sand to 3317' - cap w/5 sx cmt - shoot pipe - set
bridge at 400' - fill w/cmt slurry to surface.

PLUGGING PROPOSAL RECEIVED BY: Dist #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 8:45a DAY: 3 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Sanded to 3317' - capped w/5 sx cmt - shot 5-1/2" &
recovered 2014' - bailed to 410' - bridge set 410'-400'
- filled casing with 5-1/2 vds cmt slurry to surface.

REMARKS: open hole Plenert Construction #0608

I DID OBSERVE THIS PLUGGING.

Phil Worley
Phil Worley (AGENT)

INVOICED
JUL 18 1990

DATE: 7-27-90
WICHITA, KANSAS
NO. 2877
7-3

FORM CP-2/3
REV. 3/90