

1031364

10-11

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 101-21,713-00-00
NW NE SW, SEC. 5, T 16 S, R 27 W/EX
2310 feet from S section line
1650 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5015
Operator: Hellar Drilling Co., Inc.
Name:
Address 125 N. Market, Ste. 1422
Wichita, KS 67202

Lease Name Christian Church Well # 3
County Lane 146.97
Well Total Depth 4522 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SMD Well O&A X
Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684
Address 150 N. Main, Ste. 801, Wichita, KS 67202-1383

Company to plug at: Hour: Day: 11 Month: 10 Year: 1995

Plugging proposal received from Gary Fisher
(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2009-45'
1st plug at 2010' with 50 sx cement, 2nd plug at 1140' with 80 sx cement,
3rd plug at 710' with 40 sx cement, 4th plug at 300' with 40 sx cement,
5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4 a.m. Day: 11 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2010' with 50 sx cement,
2nd plug at 1140' with 80 sx cement,
3rd plug at 710' with 40 sx cement,
4th plug at 300' with 40 sx cement, 5th plug at 40-0' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

RECEIVED
OCT 16 1995
10-16-1995
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-19-95
INV. NO. 43832
10-11

Signed Steve Durrant (TECHNICIAN)

EFFECTIVE DATE: 10-3-75

State of Kansas

FORM MUST BE SIGNED

DISTRICT # 1
SGA? Yes No

NOTICE OF INTENTION TO DRILL 101-21,713-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 10 1 95
month day year

Spot NE SW Sec 5 Twp 16 S, Rg 27 XX West

OPERATOR: License # 5015
Name: Heller Drilling Co., Inc.
Address: 125 N. Market #1422
City/State/Zip: Wichita, KS, 67202
Contact Person: Don Heller
Phone: (316) 267-2845

CONTRACTOR: License #: 30684
Name: Abercrombie RTD, Inc.

Well Drilled For: Well Class: Type Equipment:
XX Oil ... Enh Rec ... Infield .XX Mud Rotary
... Gas ... Storage .XX Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If OAWO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth ...

2310' feet from South / North line of Section
1650' feet from East West line of Section
IS SECTION XX REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Lane
Lease Name: CHRISTIAN CHURCH Well #: 3
Field Name: ...
Is this a Prorated/Spaced Field? ... yes X no
Target Formation(s): LKC
Nearest lease or unit boundary: 330'
Ground Surface Elevation: Unknown feet MSL
Water well within one-quarter mile: ... yes XX no
Public water supply well within one mile: ... yes XX no
Depth to bottom of fresh water: 140' IB
Depth to bottom of usable water: 1100'
Surface Pipe by Alternate: ... 1 XX 2
Length of Surface Pipe Planned to be set: 230'
Length of Conductor pipe required: -0-
Projected Total Depth: 4450'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond XX other

Directional, Deviated or Horizontal wellbore? ... yes XX no
If yes, true vertical depth: ...
Bottom Hole Location: ...

Will Cores Be Taken? ... yes XX no
If yes, proposed zone: ...

Exp. 3/28/96 AFFIDAVIT 200' Alt. II Req.
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

- 1. Notify the appropriate district office prior to spudding of well:

Pusher Long Fish
SPUD DATE 10/4/95 INIT. SD
LENGTH SURFACE PLANNED 250'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 7/8 @ 257 CONDUCTOR
ANHYDRITE T-2009 B-2043 ELEVATION
TD 4522 FORMATION MISS
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 2010 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 1190 Ft. W/ 80 SX
3 1/2, 1/2 Plug @ 710 Ft. W/ 40 SX
4 Bottom Surface @ 300 Ft. W/ 40 SX
5 40' Plug @ 40-0 Ft. W/ 10 SX
RAT HOLE CIRC/W/ SX MOUSE HOLE W/O SX
WATER WELL SX (Irr. Well Fond X) Hauling
TECHNICIAN SD DATE 10-9-95
TYPE OF CEMENT White Port 5% Fly Ash
STARTING TIME (AM/PM) DATE 10/11/95
COMPLETION TIME 4 (AM/PM) DATE 10/11/95
CEMENT COMPANY Allied

Vertical text on right margin: 235 SX 10/11/95