

1 070280

JAN 06 1987

API NUMBER 15-101-20,474-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

E/2 SE SE, SEC. 4, T 16 S, R 27 W/~~E~~  
660 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Lang "D" Well # 2

Operator: Donald C. Slawson

County Lane Lane 149.34

Name & Address 200 Douglas Building

Well Total Depth 4595 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 369

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 6 Month: 1 Year: 1987

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4594' PBTD 4519' Perfs at 4398-4408' Elevation 2629'GL

1st plug sand back to 4335' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 6 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4335' and dump 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION  
01-09-1987  
JAN 9 1987

Maximum pressure 700 psi and shut in 200 psi.

Remarks: Recovered 1700' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied. CONSERVATION DIVISION  
(If additional description is necessary, use BACK of this form.) Wichita, Kansas

**INVOICED** (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 1-20-87

Signed Don Goodson  
(TECHNICIAN)

INV. NO. 15945