

1 060775

API NUMBER 15- 101-21,276 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NE, SEC. 4, T 16 S, R 27 W/E
4950 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Thies Well # 1

Operator: Chief Drilling Co., Inc.
Name & Address 151 North Main, Suite 700
Wichita, KS 67202

County Lane Lane 144.30
Well Total Depth 4440 Mississippi feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 404'

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 5:00 pm Day: 18 Month: January Year: 19 86

Plugging proposal received from Harold Dinkle

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2519
Anhydrite 1945-1980

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 50 sx cement

3rd plug at the base of the Dakota and into the surface pipe with 80 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 7:00 pm Day: 18 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1970' with 50 sx cement, 2nd plug at 960' with 50 sx

cement, 3rd plug at 600' with 80 sx cement, 4th & 5th plugs - solid bridge - hulls - plug

at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15

sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 27 1986
01-27-1986
CONSERVATION DIVISION

Remarks: Used 60/40 Pozmix 3% cc 2% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (If not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE FEB 5 1986

INV. NO. 12332