

1 031099

9-8

API NUMBER 15-101-21,558-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW NW, SEC. 1, T. 16 S, R. 27 W

4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name Karilyn Well # 1

Operator: Energy Exploration, Inc.

County Lane 146.31

Name & Address 1002 S. Broadway

Well Total Depth 4502 feet

Wichita, KS 67211

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 1 p.m. Day: 8 Month: 9 Year: 19 90

Plugging proposal received from Harvey Moore

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1982-2006!

1st plug at 2000' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 50 sx cement, 4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30 p.m. Day: 8 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2000' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 240' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmiz 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

INVOICED

DATE: SEP 17 1990

INV. NO. 29329

SEP 11 1990
09-11-1990
CONSERVATION DIVISION
Wichita, Kansas

Signed Steve Perout (TECHNICIAN)

EFFECTIVE DATE: 8-27-90

15-101-21558-00-00

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas

FORM MUST BE SIGNED

NOTICE OF INTENTION TO DRILL 101-21,558

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 08 20 90
month day year

SE NW NW Sec 1 Twp 16 S, Rg 27 East West

OPERATOR: License # 5063
Name: Energy Exploration, Inc.
Address: 1002 S. Broadway
City/State/Zip: Wichita, Kansas 67211
Contact Person: Brad Lehl
Phone: 316/267-7336

4290 feet from South line of Section
4290 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5422
Name: Abercrombie Drilling, Inc.

County: Lane
Lease Name: Karilyn Well #: 1
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:
 Oil ... Inj ... Infield Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal Wildcat ... Cable
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes no
Target Formation(s): Mississippian
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2564 feet MSL
Domestic well within 330 feet: ... yes no
Municipal well within one mile: ... yes no
Depth to bottom of fresh water: 100'
Depth to bottom of usable water: 1270'
Surface Pipe by Alternate: ... 1 2
Length of Surface Pipe Planned to be set: 200'
Length of Conductor pipe required: none
Projected Total Depth: 4460
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
... well ... farm pond other

If OAWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

DWR Permit #: _____
Will Cores Be Taken?: ... yes no
If yes, proposed zone: _____

Directional, Deviated or Horizontal wellbore? ... yes no
If yes, total depth location: _____

Exp. 2/22/91

AFFIDAVIT

200' Alt. II Reg.

RECEIVED

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

SEP 11 1990

09-11-1990

CONSERVATION DIVISION
Wichita, Kansas

Pusher Harvey Moore
 SPUD DATE 8-30-90 INIT. MS
 LENGTH SURFACE PLANNED 200'
 RESERVE PIT STATUS- REMOVE FLUID LINED
 after salt sect. bbls. when done bbls.
 RATHOLED AHEAD? Y N SIZE HOLE
 SURFACE PIPE 5 7/8" @ 215 CONDUCTOR
 ANHYDRITE T- 1982 B- 2006 ELEVATION
 TD 4502 FORMATION _____
 RAN PIPE @ SX DV TOOL _____ ALT II DONE
 _____ SX Y N
 Arbuckle Plug @ _____ Ft. W/ _____ SX
 Hug./Council @ _____ Ft. W/ _____ SX
 Anhydrite Base @ 2000 Ft. W/ 50 SX
 1/2 Base Anhy. @ 1300 Ft. W/ 80 SX
 1/2, 1/2 Plug @ 700 Ft. W/ 50 SX
 Bottom Surface @ 240 Ft. W/ 40 SX
 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
 WATER WELL _____ SX (Irr. Well _____ Pond _____)
 Hauling _____
 TECHNICIAN R. L. DATE 9-7-90
 TYPE OF CEMENT 60/40 6%
 STARTING TIME 1:00 (AM/PM) DATE 9-8-90
 COMPLETION TIME 10:30 (AM/PM) DATE 9-8-90
 CEMENT COMPANY BS Services