

1051912 3-23

101-21,698-0000

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-  
100' W & 75' N  
N/2 S/2 SE, SEC. 31, T 16 S, R 27 W/E

1065 feet from S section line  
1420 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30870  
Operator: Reynolds-Rexwinkle Oil, Inc.  
Name & Address: 212 N. Market, Ste. 402  
Wichita, KS 67202

Lease Name Munsell Well # 1  
County Lane  
Well Total Depth 4700 152.75 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard JV, Inc. License Number 4958

Address P.O. Box 1009, McPherson, KS 67460-1009

Company to plug at: Hour: 3:30 p.m. Day: 23 Month: 3 Year: 1995

Plugging proposal received from Arnie Hess

(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2121-66'

1st plug at 2160' with 50 sx cement, 2nd plug at 1300' with 80 sx cement,

3rd plug at 660' with 50 sx cement, 4th plug at 280' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7 p.m. Day: 23 Month: 3 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 2160' with 50 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 660' with 50 sx cement,

4th plug at 280' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
did not observe this plugging.

DATE 3-30-95

INV. NO. 42495

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
03-28-1995  
MAR 28 1995

FOR KCC USE:

EFFECTIVE DATE: 3-13-95

DISTRICT #

Yes  No

State of Kansas

101-21,698-~~00-00~~ 7-00

FORM C-1 7/9

FORM MUST BE TYPE

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date March 15, 1995 100' W Spot 75' N N/2 S/2 SE. Sec 31. Twp 16. S. Rg 27. East  West

OPERATOR: License # 30870  
Name: Reynolds-Rexwinkle Oil, Inc.  
Address: 212 N. Market #402  
City/State/Zip: Wichita, Kansas  
Contact Person: Dan Reynolds  
Phone: 316-269-1233

CONTRACTOR: License #: 4958  
Name: Mallard JV, Inc.

Well Drilled For: Well Class: Type Equipment:

Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 OWD  Disposal  Wildcat  Cable  
 Seismic;  # of Holes  Other

If OWD: old well information as follows:

Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_  
Comp. Date: \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore?  yes  no

If yes, true vertical depth: \_\_\_\_\_

Bottom Hole Location: \_\_\_\_\_

Exp. 9/8/95

AFFIDAVIT

.....1065..... feet from South ~~XXX~~ (line of Section  
.....1420..... feet from East ~~XXX~~ (line of Section  
IS SECTION X REGULAR \_\_\_\_\_ IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Lane

Lease Name: Munsell Well #: 1

Field Name: Wildcat

Is this a Prorated/Spaced Field?  yes  no

Target Formation(s): Mississippi

Nearest lease or unit boundary: 1065

Ground Surface Elevation: 2700 feet MSL

Water well within one-quarter mile:  yes  no

Public water supply well within one mile:  yes  no

Depth to bottom of fresh water: 250-100

Depth to bottom of usable water: 100-1250

Surface Pipe by Alternate:  1  2

Length of Surface Pipe Planned to be set: 250

Length of Conductor pipe required: none

Projected Total Depth: 4700

Formation at Total Depth: Mississippi

Water Source for Drilling Operations:

well  farm pond  other

DNR Permit #: \_\_\_\_\_

Will Cores Be Taken?  yes  no

If yes, proposed zone: \_\_\_\_\_

200' Alt. II Req.

RECEIVED

KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following information is true and correct:

*3.23 - slot finished*

Pusher Carroll / Annie Hess

SPUD DATE 3-15-95 INIT. SD

LENGTH SURFACE PLANNED 250'

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 3/8" @ 2-59 CONDUCTOR  
ANHYDRITE T- 2121 B- 2166 ELEVATION

TD 4700 FORMATION \_\_\_\_\_  
RAN PIPE @ SX DV TOOL \_\_\_\_\_ ALT II DONE \_\_\_\_\_  
\_\_\_\_\_ SX Y N

Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX

Anhydrite Base @ 2160 Ft. W/ 50 SX

1/2 Base Anyh. @ 1300 Ft. W/ 80 SX

1/2, 1/2 Plug @ 660 Ft. W/ 50 SX

Bottom Surface @ 280 Ft. W/ 40 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_

TECHNICIAN RAY DATE 3-20-95

TYPE OF CEMENT 40/40/40 6% grt 1/4 Flostal

STARTING TIME 3:30 (AM/PM) DATE 3-23-95

COMPLETION TIME 1:00 (AM/PM) DATE 3-23-95

CEMENT COMP \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 23 1995  
MICHIGAN