

To: 1 051597  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-16

API NUMBER 15-101-21,639-00-00 83  
NW NE NW, SEC. 31, T 16 S, R 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Operator: Pickrell Drilling Company Inc.  
Name &  
Address 110 N. Market, Ste. 205  
Wichita, KS 67202

4950 feet from S section line

3630 feet from E section line

Lease Name Becker "L" Well # 1

County Lane 151.94

Well Total Depth 4675 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Company Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 15 Month: 11 Year: 1992

Plugging proposal received from Doyle Folkerts

(company name) Pickrell (phone) 316-272-8427

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2166-86'

1st plug at 2180' with 50 sx cement, . 2nd plug at 1380' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 330' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:15 a.m. Day: 16 Month: 11 Year: 1992

ACTUAL PLUGGING REPORT 1st plug at 2180' with 50 sx cement,

2nd plug at 1380' with 80 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 330' with 40 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

I ~~did not~~ observe this plugging.

DATE 12-4-92

INV. NO. 36964

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
CORPORATION COMMISSION

NOV 17 1992  
11-17-1992

EFFECTIVE DATE:

DISTRICT #

SEA? Yes. No

State of Kansas

101-21,639

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10 - 30 - 92 month day year

360' East NW..NE..NW. Sec .31. Twp .16. S. Rg 27.. X West

OPERATOR: License # 5123 Pickrell Drilling Co., Inc. Name: 110 N. Market, Suite 205 Address: Wichita, Kansas 67202 City/State/Zip: Don Beauchamp Contact Person: 316-272-8427 Phone:

4950 feet from South / North line of Section 3630 feet from East / West line of Section IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Lane Lease Name: Becker "L" Well #: 1 Field Name: LS NE

Is this a Prorated/Spaced Field? yes X no Target Formation(s): Lansing-Marmaton-Johnson Zone

Nearest lease or unit boundary: 330' Ground Surface Elevation: 2731' feet MSL

Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 45' 230' Depth to bottom of usable water: 1110' 1350'

Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 325'

Length of Conductor pipe required: None Projected Total Depth: 4650'

Formation at Total Depth: Mississippian Water Source for Drilling Operations:

well X farm pond other DWR Permit #: Will Cores Be Taken? yes X no

If yes, proposed zone: 260' Alt. II Req.

CONTRACTOR: License # 5123 Pickrell Drilling Co., Inc. Name:

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OUVU ... Disposal X Wildcat ... Cable ... Seismic; ... # of Holes ... Other

If OUVU: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth:

Bottom Hole Location:

Exp. 4/22/93

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Poyle F. SPUD DATE 10-2-92 INIT. CA LENGTH SURFACE PLANNED 300' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8 @ 299 CONDUCTOR ANHYDRITE T- 2166 B- 2186 ELEVATION TD 4675 FORMATION MISS RAN PIPE @ DV TOOL ALT II DONE SX Y N Ar buckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 2180 Ft. W/ 50 SX 1/2 Base Anyh. @ 1380 Ft. W/ 80 SX 1/2, 1/2 Plug @ 700 Ft. W/ 40 SX Bottom Surface @ 330 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN A. L DATE 11-13-96 TYPE OF CEMENT 60/40 per 6% gel 1/4 floccul STARTING TIME 11:00 (AM/PM) DATE 11-15-92 COMPLETION TIME 11:15 (AM/PM) DATE 11-16-92 CEMENT COMPANY