

1 070205

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,680-00-00

SE NW SE SEC. 30, T 16 S, R 27 W/E

1650 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5158

Lease Name Hanks "H" Well # 1

Operator: Donald C. Slawson

County Lane 151.61

Name & Address 200 Douglas Building

Well Total Depth 4665 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. Well Service License Number 4072

Address P.O. Box 346, No. 283 Hwy, Ness City, KS 67560

Company to plug at: Hour: 5:00 pm Day: 8 Month: August Year: 1986

Plugging proposal received from Clint Base

(company name) Plains Inc. Well Service (phone) (913) 798-3995

were: 4 1/2" at 4664' PBD at 4617' Perfs at 4090-92'; 4250-51'

1st plug sand back to 4040' and dump 4 sx cement and 1 sack cc on top of sand through bailer

2nd plug rip 4 1/2" casing at 1180', swab to 1400', fill 4 1/2" with 50 sx cement, and

pump 100 sx cement down 8 5/8".

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 8:30 pm Day: 8 Month: August Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 4040' and dumped 4 sx cement and

1 sack cc on top of sand through bailer, 2nd plug ripped 4 1/2" casing at 1180',

swabbed to 1400', filled 4 1/2" casing with 50 sx cement, and pumped 100 sx cement

down the 8 5/8" casing.

Remarks: Used ATL cement pumped by Allied. Could not pump into the 4 1/2" casing.
If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 12 1986

INV. NO. 14712

8-8

Signed Dan Goodrow
(TECHNICIAN)

AUG 12 1986
08-12-1986