

15-169-00584-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Saline County, Sec. 17 Twp. 16 Rge. 3 W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Fall & Wolfe Oil Co.
Lease Name Nelson Well No. I
Office Address Bx 7447 Tulsa, Oklahoma 74105
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-22 19 53
Application for plugging filed 3-22 19 72
Application for plugging approved 3-23 19 72
Plugging commenced 3-27 19 72
Plugging completed 3-30 19 72
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3461' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3461' to 3440'. Dumped 3 sx of cement. Mudded hole to 265'. Made 10' of rock bridge. Dumped 4 Yrds. Of Ready-Mix Cement, filling to the bottom of the celler.

RECEIVED
STATE CORPORATION COMMISSION
APR 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Art Lamb

2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of March 19 72

My commission expires January 1, 1974

Judy Lamb
Notary Public.



WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY
15-169-00584-00-00


out farm

Company- ATLANTIC REFINING CO.
Farm- Nelson No. 1

SEC. 17 T. 16 R. 31
CSU No.

Total Depth. 3461
Comm. 5-6-53 Comp. 5-22-53
Shot or Treated.
Contractor. Keating Drllg.
Issued. 7-11-53

County Saline
KANSAS



Elevation. 1887 D.F.

Production. State test 40 bbls.

CASING:

8 5/8" 390 RKB com. w/402 sx.
4 1/2" 3458 RKB com/200 sx.

Figures indicate Bottom of Formations.

shale & sand	320
shale & shells	350
shale & lime	390
lime	395
sand & shale	790
shale & shells brkn	
lime	1035
shale	1100
lime & shale	1150
shale	1610
lime brkn, shale & shells	1845
lime brkn	1955
lime & shale	2100
lime brkn	2205
shale & lime	2302
lime	2350
lime & shale	2545
lime brkn	2745
lime & shale	2835
lime brkn	3004
lime	3065
lime & shale cherty	3135
lime	3209
shale & shells	3253
shale	3365
shale, sand, shale	3458
dolo.	3461
Total Depth	

Handwritten calculation:
3458
- 1387

2071

Tops: Scout	
Brown lime	2226
Lansing	300
Mississippi	2962
Kinderhook	3224
Wizner	3415
Maquoketa	3418
Maquoketa dolo.	3456

acidized w/2000 gals. oil producing from
Maquoketa Dolo. 3458-3461.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1972
CONSERVATION DIVISION
Wichita, Kansas