

15-169-00586-00-017


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Saline County, Sec. 17 Twp. 16s Rge. 3 W (E) (W)
Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Fell & Wolfe Oil Company
Lease Name J. Godfrey Oborg Well No. I
Office Address P.O. Box 7447 Tulsa, Oklahoma 74105
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 5-27 19 74
Application for plugging filed 5-24 19 74
Application for plugging approved 5-25 19 74
Plugging commenced 5-26 19 74
Plugging completed 6-12 19 74
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3464' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,636'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with snad. Sand from 3464' to 3400'. Dumped 3 sx of cement. Mudded hole to 215'. Made 15' of rock bridge. Dumped 25 sx of cement. Mudded hole to 40'. Made 10' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1974
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas, COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 19 74

My commission expires December 31, 1977



[Signature]
Notary Public.

15-169-00586-00-01

THE ATLANTIC REFINING COMPANY
830 Kennedy Building
Tulsa, Oklahoma

WELL LOG

J. Godfrey Oberg No. 1

RECEIVED
STATE CORPORATION COMMISSION
MAY 28 1974
CONSERVATION DIVISION
Wichita, Kansas

Location: C NW NW of 17-16S-3W, Saline County, Kansas.

Lease Number: KS-12,175

Elevations: RKB 1387', DF 1385', -GL 1383'.

Spudded: May 19, 1953

Reached T. D.: May 27, 1953

Contractor: Keating Drilling Company

Casing Record:

Ran 9 joints (373') of 8-5/8" OD 24# J-55 seamless casing and set at 380' RKB with 100 sacks regular cement with 2% calcium chloride.

Ran 111 joints (3455') of 4-1/2" OD 9.5# H-40 ST&C 8 RT seamless casing and set at 3461' with 130 sacks Pozmix.

FORMATION RECORD:

Surface clay and sand	0'- 40'
Sand and shale	40'- 120'
Shale	120'- 150'
Shale and sand	150'- 180'
Shale	180'- 280'
Shale and sand	280'- 440'
Lime and shale	440'- 560'
Red bed	560'- 600'
Lime and shale	600'- 1080'
Shale and shells	1080'- 1345'
Sand and shale	1345'- 1695'
Shale and lime	1695'- 2085'
Broken lime	2085'- 2295'
Shale	2295'- 2307'
Lime	2307'- 2467'
Lime and shale	2467'- 2611'
Lime (hard)	2611'- 2715'
Lime (broken)	2715'- 2800'
Lime	2800'- 2975'
Shale and lime	2975'- 3050'
Lime (broken)	3050'- 3185'
Lime	3185'- 3236'
Lime and shale	3236'- 3464'

T.D. 3464'

Completions:

On July 9, 1953 produced 59.54 BO, 8% water, on 24 hour test from 3461'-3464' (Maquoketa Dolomite). Unprorated.
