

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-23,026 -00-00

LEASE NAME Carter

WELL NUMBER 1

2310 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 4 TWP. 16 RGE. 25 ~~W~~ or (W)

COUNTY Ness

Date Well Completed 5-12-86

Plugging Commenced 5-12-86

Plugging Completed 5-13-86

LEASE OPERATOR L. D. Drilling, Inc.

ADDRESS Route 1, Box 183-B Great Bend, KS 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 6039

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? operator to be filed by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4509'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 1960' w/40 sacks 50/50 pozmix 4% gel thru drill pipe

Next Plug: @ 1200' w/80 " " " " " "

Next Plug: @ 400' w/50 " " " " " "

Top Plug: @ 40' Bridged & Plug w/10 sacks cement 15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address Box 877 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) Box 877 Great Bend, KS 67530

RECEIVED
STATE CORPORATION COMMISSION


MAY 19 1986

5-19-86
CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 15 day of May, 1986

Dorothy M Hague
Notary Public

My Commission Expires: DOROTHY M. HAGUE



DRILLER'S WELL LOG

DATE COMMENCED: May 6, 1986
DATE COMPLETED: May 12, 1986

L. D. Drilling, Inc.
CARTER #1
NE NW SE
Sec. 4, T16S, R25W
Ness County, Ks.

ELEVATION: 2524 K.B.

0 - 1930' Surface Soil, Clay, Sand, Shale
1930 - 1965' Anhydrite
1965 - 3823' Shale, Lime
3823 - 3827' Shale
3827 - 3863' Lime & Shale
3863 - 4105' Lime
4105 - 4170' Shale
4170 - 4399' Lime
4399 - 4482' Sand
4482 - 4509' Lime & Chert
4509' RTD

FORMATION DATA

Anhydrite	1930'
Heebner	3823'
Lansing	3863'
Stark	4105'
Kansas City	4170'
Fort Scott	4374'
Cherokee	4399'
Mississippi	4482'
RTD	4509'

Surface Pipe: Set new
8-5/8", 23# pipe @378'
w/215 sacks 60/40 pozmix
2% gal 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, doessswear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 15 day of May 1986

Dorothy M Hague
Notary Public



STATE CORPORATION COMMISSION
MAY 19 1986
CONSERVATION DIVISION
Wichita Kansas