

LEASE NAME GIESS

WELL NUMBER #1

3300 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 2 TWP. 16S RGE. 25 ~~W~~ W

COUNTY Ness

Date Well Completed 7-12-88

Plugging Commenced 7-12-88

Plugging Completed 7-12-88

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Double Eagle Exploration Inc.

ADDRESS 512 Century Plaza, Wichita, Kansas 67202

PHONE# (316) 267-3316 OPERATORS LICENSE NO. 6009

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 12th, 1988 (date)

by Dan Goodrow (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom SEP 20 1988

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

CONSERVATION DIVISION  
 Wichita, Kansas

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Plug @ 1990' w/50 sx., Plug @ 1150' w/75 sx., Plug @ 390' w/40 sx., Plug @ 40' w/10 sx., 15 sx. rathole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rains & Williamson Oil Co., Inc. License No. 682

Address 220 W. Douglas, Suite 435, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Wilson Rains, President of Rains & Williamson Oil Co., (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Wilson Rains

(Address) 220 W. Douglas, Suite 435, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 18th day of July, 19 88

Juanita M. Green  
 Notary Public

My Commission Expires: 10-4-91



DRILLER'S LOG

COMPANY: Double Eagle Exploration, Inc.

SEC. 2 T. 16S R. 25W

WELL NAME: GIESS #1

LOC. C SW NE

COUNTY: Ness

RIG NO. #2

TOTAL DEPTH 4546'

ELEVATION 2550 GL 2559 KB

COMMENCED: 7-5-88

COMPLETED: 7-12-88

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 378' w/210 sx. 60-40 poz., 2% gel, 3% cc.

PRODUCTION: D&A

LOG

(Figures Indicate Bottom of Formations)

Shale	1180
Sand and Shale	1835
Shale	2190
Shale and Lime	2600
Lime and Shale	4440
Lime	4520
Shale and Lime	4546
Rotary Total Depth	4546

RECEIVED  
STATE CORPORATION COMMISSION

JUL 21 1988

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
COUNTY OF SEDGWICK )

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the  
GIESS #1 well.

JUANITA M. GREEN  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXPIRES 10-4-91

Wilson Rains  
WILSON RAINS

Subscribed and sworn to before me this 18th day of July, 1988.

My Appointment Expires:  
October 4, 1991

Juanita M. Green  
Juanita M. Green - Notary Public