


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Ness County, Sec. 2 Twp. 16S Rge. (E) 25 (W)
Location as "NE/CNW/SW" or footage from lines C/NE SE
Lease Owner Okmar Oil Company
Lease Name Kaler Well No. 3
Office Address 1130 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 21 19 70
Application for plugging filed July 21 19 70
Application for plugging approved July 21 19 70
Plugging commenced July 21 19 70
Plugging completed July 21 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo J. Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4534 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	278'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Plugged hole as follows: Plugged at 800' with 70 sacks of regular cement; plugged at 270' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 6:15 P. M. July 21, 1970.


STATE RECEIVED
JUL 24 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)



Subscribed and sworn to before me this 22nd day of July, 19 70
Elaine H. Taylor Notary Public.
My commission expires September 14, 1973

D R I L L E R S L O G

#3 Kaler

CASING RECORD: 278' or new 8-5/8" surface casing.	COMPANY: Okmar Oil Company	DESCRIPTION: C/NE SE Section 2-16S-25W Ness County, Kansas
TOTAL DEPTH: 4534'	CONTRACTOR: Strata Drilling, Inc.	ELEVATION: 2539' KB
	COMMENCED: July 13, 1970	
	COMPLETED: July 21, 1970	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Sand & Post Rock	0	309	Ran 278' of new 8-5/8" surface casing; set and cemented at 278' with 160 sacks of regular cement, 2% gel and 3% C. C. Plug down at 9:45 P. M. July 13, 1970.
Blue Shale	309	434	
Shale w/Sand Streaks	434	760	
Red Bed, Shale, Shells & Sand	760	1160	
Shells & Red Bed	1160	1334	
Anhydrite	1334	1346	
Red Bed	1346	1417	
Dakota Sand	1417	1695	
Red Bed, Shells & Shale	1695	1727	
Shale	1727	1937	
Anhydrite	1937	1974	
Shale	1974	2102	
Shale & Shells	2102	2542	
Broken Lime, Shells & Shale	2542	2627	
Lime & Shale	2627	4076	
Lime	4076	4420	
Lime & Shale	4420	4472	
Lime & Chert	4472	4510	
Lime	4510	4534	

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1970
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Rotary Total Depth: 4534'

Plugged hole as follows: Plugged at 800' with 70 sacks of regular cement; plugged at 270' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 6:15 P. M. July 21, 1970.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 22nd day of July, 1970.

NOTARY PUBLIC
ELAINE H. TAYLOR
My Commission Expires:
December 14, 1973
BARTON COUNTY, KANSAS

Elaine H. Taylor
Elaine H. Taylor, Notary Public