

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Ness County. Sec. 12 Twp. 16 Rge. 25 (E) (W) X

Location as "NE/CNW/SE/SW" or footage from lines NW NW NW
Lease Owner D. G. Hansen Trust
Lease Name Clyne Well No. #1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 10-24-72 19
Plugging completed 10-30-72 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Leo Massey

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4480' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	4475'	2860.77'
				8 5/8"	294'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made bottom hole plug back with sand to 4460'. Mixed and ran 5 sacks cement thru dump bailer.

Squeezed with 3 sacks hulls - 25 sacks gel - 2 sacks hulls - 70 sacks cement. 10 sacks gel and 70 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 1 1972

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Southwest Casing Pulling Co.
Address Box 364 Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

Southwest Casing Pulling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec
Box 364 Great Bend, Kansas (Address)

Subscribed and sworn to before me this 31 day of October, 1972



Sidney D. Miller
Notary Public.

My commission expires 24 October 1976

W E L L L O G

OPERATOR: DANE G HANSEN TRUST

WELL NAME: CLYNE #1 LOCATION: NW NW NW SEC 12-16S-25W

COUNTY: NESS STATE: KANSAS

WELL COMMENCED: APRIL 5, 1971 WELL COMPLETED: APRIL 15, 1971

ELEVATION: 2508 K B TOTAL DEPTH: 4480

PRODUCTION: PRODUCING RIG NO: 1

CASING - 8-5/8": SET 294.44' (16 JTS) 8 5/8" 28# SURFACE CASING USED

5-1/2": SET 4499.24' (144 JTS) 5 1/2" OD CASING.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	500	SHALE		
500	1690	SHALE & SAND	1 1/2° @ 1718'	
1690	1865	SAND		
1865	1897	SHALE & SHELLS		
1897	1932	ANHYDRITE		
1932	2090	SHALE & LIME	3/4° @ 2020'	
2090	2610	SHALE & SHELLS		
2610	3935	LIME & SHALE	1 3/4° @ 2803'	
3935	4040	LIME		
4040	4115	LIME & SHALE		
4115	4480	LIME		
RTD	4480			DST #1 4474'-4480'

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1972

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway

G. F. Galloway

Subscribed and sworn to, before me, this 19th day of April, 1971.

NOTARY PUBLIC, DEC. 7, 1971

Phyllis Buchanan
PHYLLIS BUCHANAN - NOTARY PUBLIC

