

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-135-21686-00-00

API NUMBER 9-10-79

LEASE NAME Marjorie

WELL NUMBER 1

SPOT LOCATION SW SW NE

SEC. 13 TWP. 16 RGE. 25 (E) or (W)

COUNTY Ness

Date Well Completed 9-10-79

Plugging Commenced 7-7-89

Plugging Completed 7-7-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Beren Corp.

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5364

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. 1 Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4504

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface	0	271	8 5/8		
	Casing	0	4497	4 1/2		

RECEIVED  
STATE CORPORATION COMMISSION

III 21 1989 7-21-89

CONSERVATION DIVISION  
None Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Rig up BJ and run wire line. Check fluid level. Fluid 1260' from surface. Load hole. Take inj. rate 3 BPM 600#. Pump 600# hullis, 200 sks. cement down casing. Max. pressure 1000#. Shut in press 900#. Pump 40 sks. cement down annulus. Max. pressure 500#. Shut in pressure 350#. Put 10 sks. cement down rat hole. Well plugged.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Beren Corp. License No. 5364  
Address Box 723 Hays, Kansas 67601

BJ Titan cementers

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford  
(Address) Box 723 Hays, Mo 67601

ROSEMARY SMITH  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPT. EXP. MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 20 day of July, 1989

Rosemary Smith  
Notary Public

My Commission expires: 5/1/1991

Form CP-4 /  
Revised 06-83